




Contents

- 1.) General Information
- 2.) Linac
- 3.) Booster Synchrotron
- 4.) Storage Ring

The Accelerator Complex

3 GeV
Storage
Ring

Accelerator complex of ALBA: We followed the concept of the SLS to have the booster and the storage ring in the same tunnel. The preinjector is a 100 MeV Linac




BTS

Courtyard

100 MeV Linac

LTB


3 GeV
Booster
Synchro-
tron









Contents

- 1.) General Information
- 2.) Linac
- 3.) Booster Synchrotron
- 4.) Storage Ring





Conditions at the exit of the Linac:

$\epsilon(x) = 65.1$ nmard


$\beta(x) = 10.4$ m/rad

$\alpha(x) = 1.98$

$\epsilon(y) = 46.6$ nmard

$\beta(y) = 8.46$ m/rad

$\alpha(y) = 1.87$




Contents

- 1.) General Information
- 2.) Linac
- 3.) Booster Synchrotron
- 4.) Storage Ring


3 GeV Booster
gradient dip.,
with built-in
sextupole.
Circumference:
249.6 m

4 superperiods:
32 long dip. 2 m
8 short dip. 1 m
60 quads in
4 families

Emittance
10 nm·rad




The lattice is a TME-structure
The ALBA synchrotron should have the smallest emittance in the world





Q(x) is given by QH02 and Q(y) is given by the bends. All the other quads for fine tuning

Design working point: $Q_x = 12.42$, $Q_y = 7.38$




**Good agreement
with the model**






We don't understand the movement of the working point. It has to be investigated




9th October 2011



Each 14th shot is a “Bad Shot”

1st extracted Beam from the Booster Synchrotron, 28th of October 2010




$\sigma(x) = 0.86 \text{ mm}$, $\sigma(y) = 0.19 \text{ mm}$
 $\epsilon(x) = 13 \text{ nmrad}$, $\epsilon(y) = 2,6 \text{ nmrad}$

We are 30 % off to the theoretical emittance and have a coupling factor of roughly 20%.

Contents

- 1.) General Information
- 2.) Linac
- 3.) Booster Synchrotron
- 4.) **Storage Ring**





4 long: $\sigma(x) = 300\mu\text{m}$, $\sigma(y) = 16.2\mu\text{m}$




12 medium: $\sigma(x) = 147\mu\text{m}$, $\sigma(y) = 7.6\mu\text{m}$



8 short: $\sigma(x) = 362\mu\text{m}$, $\sigma(y) = 15.1\mu\text{m}$


$Q(x) = 18.18$
 $Q(y) = 8.37$
 $\varepsilon(x) = 4.5\text{ nmrad}$
 $\alpha = 8.83 \cdot 10^{-4}$
 $\delta E/E = 1.05 \cdot 10^{-3}$

Change of Bending Gradient




Change of k-Values of the individual magnets.

Change of Bending Fringe Field Angle




Change of fringe field angle of the individual Magnets.



$C = 268.8 \text{ m}$, $Q_x = 18.183$, $Q_y = 8.395$, $\epsilon = 4.44 \text{ nmrad}$

$Rho = 6.99718$, $l = 1.373893 \text{ m}$, $k = \text{individual}$, $\phi = \text{individual}$



According to the individual characteristics of the bending magnet, the beta beating (deviation from the model) will be around $\pm 3\%$ and the settings of the power supplies will vary about $\pm 0.6\%$ from the nominal ones. These are the guide lines for the real machine

Storage Ring Commissioning

22th of November 2010:

The storage ring was assembled (without ID's) and ready for commissioning, but the CNS certificate was missing. It was decided to install the out of vacuum undulators. This means the commissioning has to be made with 3 small vacuum chambers (+/- 4 mm)

1.) Phase: Weekend 12th/13th February 2011

For this weekend we got from CNS the allowance for the storage ring injection and one turn. We realized the miss-positioning of on BTS quadrupole and had a problem with the kicker power supplies. In general no success, we broad the beam into the first bending magnet of the storage ring.

2.) Phase: March - June 2011

We got the allowance from the CNS for the commissioning of the machine at the 8th of March 2011. We commissioned the storage ring very successful until 10th of June.

Storage Ring Commissioning

June to September 2022:

Installation of the in vacuum undulators and the SCW wiggler.

Restart of the machine in the middle of September 2011

3.) Phase: September to October 2011:

Commissioning of the in vacuum undulators and the SCW.

22nd October 2011:

Start of beam line commissioning. In the morning shift machine optimisation and in the afternoon shift beam line commissioning.



➤ Recabling Quads:


✓ Sectors 1&2




✓ Quadrant 1

✓ Quadrant 2


✓ Quadrants 3&4

19h35: 1st turn !






14-Mar-2011 10:30:42



**Energy =
2.985 GeV**




**16th of March 2011:
a historical day of the ALBA – project:
the first accumulated beam at ALBA.**





**16th of March 2011:
A historical day of the ALBA – project,
The Accelerator Division is celebrating this success.**

Once the MPS was operational...






CURRENT 170.010 mA

Life Time **0h 09m** Curr*LifeT **29.8**

Filling Mode **56 b.** Avg. Pressure (mbar) **6.10e-09**

Tuesday 07-Jun-2011 20:32:38




SR Commissioning. Max Current 1



Raw orbit without correctors

Offsets of BBA included and RF frequency adjusted


Storage Ring Orbit (Difference from the Offset Orbit)




Horizontal orbit < 3mm
Vertical orbit < 2 mm













Good alignment







Injection efficiency ~ 95%

Summary of Measurements


- Tune 
- Chromaticity 
- Beam Based Alignment 
- Orbit correction, including frequency adjustment 
- LOCO measurements: 
Beta functions, dispersion and beating correction
- Beam size, emittance 
- Bunch length 
- Vacuum performance 
- Closing IDs 
- Slow orbit correction system 


(Most of these measurements were done with 10~20 mA)






The agreement between the LOCO results and the matched solution with model are pretty good. There are small differences in the short and in the middle medium straight.






The agreement between the LOCO results and the matched lattice with the model are pretty good.







Summary:
All the evaluations from:
LOCO and pinhole agree
very well. The emittance
of the storage ring is
4.6 nmrاد

Table 1: Horizontal and Vertical parameters used for the emittance calculation, and associated error bars.

	σ , μm	β , m	D , m	ϵ , nmrاد
Hor Value	59.15	0.489	0.0355	4.58
Hor Error	3%	1%	1%	10
Ver Value	27.79	24.465	0.0	0.031
Ver Error	3%	1%	0.0	7





QH01: AVER.=128.498, STEDV=0.08

QH02: AVER.=153.93, STEDV=0.1

QH03: AVER.=131.13, STEDV=0.17

QH04: AVER.=121.06, STEDV=0.08

QH05: AVER.=143.24, STEDV=0.08

QH06: AVER.=173.33, STEDV=0.13

QH08/09: AVER.=166.01, STEDV=0.42

QH07/10: AVER.=170.23, STEDV=0.24

QV01: AVER.=147.85, STEDV=0.28

QV03: AVER.=161.58, STEDV=0.97

QV03/04: AVER.=161.78, STEDV=0.81

QV02: AVER.=161.47, STEDV=0.64

QV04: AVER.=161.97, STEDV=0.62


For the horizontal focussing quadrupoles there are standard deviations up to 0.42 %, this is in a good agreement with the expected values. For the vertical focussing quadrupoles the values are going up to roughly 1 %. This is okay, but it could be a bit better. The difference between the horizontal and vertical direction is given by the variation of the gradient from magnet to magnet.




The BINP- and the ALBA team after a successful injection with a field of 2.1 T at the SCW and all the other ID's are closed.





Theoretical IDs effect (at min gap)



Pressure Profile (mbar) for ALBA machine











Current 0.000 mA

Life Time ----- (---)

Pressure 7.81e-10 mbar 



MSPD	FE04 Closed	SCW30 B = 0.064 T
MISTRAL	FE09 Closed	BEND
NCD	FE11 Closed	IVU21 30.00 mm
XALOC	FE13 Closed	IVU21 30.00 mm
CLAESS	FE22 Closed	MPW80 299.00 mm
CIRCE	FE24 Closed	EU62 270.00 mm
BOREAS	FE29 Closed	EU71 270.00 mm

Tuesday 22-Nov-2011 22:05:43

Beamline shift cancelled (22th Nov)

Summary:

- 1.) The accelerator complex of ALBA has been successful commissioned.
- 2.) The deviation from the models are in the range of percentages.
- 3.) We have to understand the transfer lines.
- 4.) The beam lines are in the commissioning phase
- 5.) We have to go to higher currents to look for instabilities and cleaning the vacuum system.
- 6.) Next year we have to install the fast orbit feedback system and
- 7.) We have to prepare for the top up injection.

**More details tomorrow in the presentation
of Marc Munoz**